		50000	DIVISION 05 - METALS									
			COLUMN WRAP									
1	A1.10		Break metal around steel column	396	10%	436	SF	$ -	$ -	$ -		
			AWNING									
2			Awning AW-1	43	10%	48	SF	$ -	$ -	$ -		
3			Awning AW-2	111	10%	122	SF	$ -	$ -	$ -		
4			Awning AW-3	47	10%	52	SF	$ -	$ -	$ -		
5			Awning AW-4	118	10%	129	SF	$ -	$ -	$ -		
6			Awning AW-5	67	10%	74	SF	$ -	$ -	$ -		
7			Awning AW-6	52	10%	57	SF	$ -	$ -	$ -		
8	A1.12, A5.10		Awning AW-7	123	10%	135	SF	$ -	$ -	$ -		
9			Awning AW-8	56	10%	61	SF	$ -	$ -	$ -		
10			Awning AW-9	62	10%	68	SF	$ -	$ -	$ -		
11			Awning AW-10	97	10%	107	SF	$ -	$ -	$ -		
12			Awning AW-11	54	10%	60	SF	$ -	$ -	$ -		
13			Awning AW-12	63	10%	69	SF	$ -	$ -	$ -		
14			Awning AW-13	71	10%	78	SF	$ -	$ -	$ -		
			Note: Manufacturer Black									
			METAL FABRICATIONS									
15	A4.00		(3'H) 1-1/2" dia. Wall mounted pre-finished handrail (Min. 2-1/4" clearance from rail to wall) - Sheet or powder coat M-1	73	10%	80	FT	$ -	$ -	$ -		
16			(36"'H) Pre-finished guardrail w/ Pre-set metal sleeve in stair pour & 1/2" Steel tubular posts - Sheet or powder coat M-1	60	10%	66	FT	$ -	$ -	$ -		
17	S2, S3		(7"x12"x12") 1/2" Steel L-plate w/ - (3-5/8" dia. x 5" long) Headed studs	272	10%	300	FT	$ -	$ -	$ -		
18			(7"x12") 1/2" Steel plate w/ - 3 (5/8" dia. x 5" long) Headed studs	577	10%	635	FT	$ -	$ -	$ -		
19			L4x4x1/4" x Cont. w/ - (3/4" dia.) Exposed bolts @24" O.C.	3886	10%	4275	LBS	$ -	$ -	$ -		
20	S2		L8x4x1/4" x Cont. LLV w/ - (3/4" dia.) Exposed bolts @24" O.C.	759	10%	835	LBS	$ -	$ -	$ -		
21			(12"x14") 1/2" Steel plate w/ - 6- (3/4" dia. x 5" long) Headed studs	207	10%	227	FT	$ -	$ -	$ -		
22	S3		L4x4x1/4"	1527	10%	1680	LBS	$ -	$ -	$ -		
			FRAMING									
23	S2		12K1 Steel joists @24" O.C.	887	10%	976	FT	$ -	$ -	$ -		
24			14K3 Steel joists @24" O.C.	2648	10%	2913	FT	$ -	$ -	$ -		
25			14K4 Steel joists @24" O.C.	175	10%	193	FT	$ -	$ -	$ -		
26			16K3 Steel Joists @24" O.C.	243	10%	267	FT	$ -	$ -	$ -		
27			16K4 Steel Joists @24" O.C.	482	10%	530	FT	$ -	$ -	$ -		
28			W12x40	4588	10%	5047	LBS	$ -	$ -	$ -		
29			W12x50	5140	10%	5654	LBS	$ -	$ -	$ -		
30			W14x68	1564	10%	1720	LBS	$ -	$ -	$ -		
31			W14x68 w/ - (1/4" thk.) Steel knife plate	3135	10%	3448	LBS	$ -	$ -	$ -		
32	S3		12K1 Steel joists @5'-0" O.C.	713	10%	785	FT	$ -	$ -	$ -		
33			14K1 Steel joists @5'-0" O.C.	439	10%	483	FT	$ -	$ -	$ -		
34			16K3 Steel joists @5'-0" O.C.	621	10%	683	FT	$ -	$ -	$ -		
35			W12x30	6696	10%	7366	LBS	$ -	$ -	$ -		
			DECK									
36	S2		0.6C, 26 GA. Metal floor deck	9383	10%	10321	SF	$ -	$ -	$ -		
37	S3		(1-1/2") Metal roof deck	9572	10%	10529	SF	$ -	$ -	$ -		
			STEEL COLUMN									
38	S1		HSS4x4x3/8 Column SC-1 - (12"x12"x1/2") Base plate	3109	10%	3419	LBS	$ -	$ -	$ -		
39			HSS5x5x1/4 Column SC-2 - (14"x14"x1/2") Base plate	6193	10%	6813	LBS	$ -	$ -	$ -		
40	S2		HSS4x4x1/4 Column SC-3 - (12"x12"x1/2") Base plate	733	10%	806	LBS	$ -	$ -	$ -		
			BEAMS									
41	S2		HSS4x4x1/4 Beam	457	10%	502	LBS	$ -	$ -	$ -		
			MISC.									
42	S3		Pre-engineered mechanical stand	427	10%	470	FT	$ -	$ -	$ -		
43			#5 @12" O.C. Top bar	96	10%	106	LBS	$ -	$ -	$ -		
			Subtotal (Concrete)									$ -
SUB TOTAL										$ -	$ -	
OVERHEAD AND PROFIT								25%		$ -	$ -	
TOTAL BASE BID										$ -	$ -	

General Exclusions: Any kind of controlled inspection, contaminated material, architect and engineering fees, security, building charges, sign off, asbestos removal, protection of adjoining building (if any), any work not mentioned above.

General Notes: The prices used while preparing the estimate were taken from RSMeans online i.e. the standard pricing & the company is not responsible for any kind of variations in the prices. So, it is preferred to review the prices.